



INDIRA GANDHI UNIVERSITY, MEERPUR, REWARI

(A State University Established under Haryana Govt. Act. 29 of 2013)

DETAILED NOTICE INVITING QUOTATION

Name of the Work:- P&F of GI Sheet along with brickwork in the Lift area of the Central Library at IGU, Meerpur.

Approx Amount: Rs. 74,500/-

Time limit : 10 Days

Sr. No./ HSR No.	Description of Item	Quantity	Rates	Unit
1/13.18	Corrugated G.I. sheet roofing 0.80mm thick fixed with galvanized iron 'J' or 'L' hooks, 10mm dia. G.I. limpet and bitumen washers complete, excluding the cost of purlins, rafters and trusses.	59.04	Rs. 137.40+300% CP	Per Sqm
2/11.29+Note (VI)a	1 st class brick work laid in Cement, stone dust (from crusher) mortar 1:4 in 4 th storey.	1.72	Rs. 490.40+600% CP	Per Cum
3/15.7+Note (i)	12mm thick cement plaster 1:6	7.47	Rs. 11.19+500% CP	Per Sqm
4/15.12	15mm thick cement plaster 1:6 on the rough side of single or half brick wall.	7.47	Rs. 13.64+500% CP	Per Sqm
5/17.29	P&F hard drawn steel wire fabric 75mmx25mm rectangular mesh with 3.25mm dia. wire fixed on chowkats with 25mm thick kail wood cover molding of full width.	3.96	Rs. 132.65+300% CP	Per Sqm
6/18.12	WI and M.S. (Using angles, flats, square bars, tee and channels) ladders, grills, grating frames, window guards, iron doors openable or fixed.	4.47	Rs.1040.35+500% CP	Per Qtl.
7/NS	Dismantling & shifting of 2.5 to 3.0 mm thick existing fiber sheet up to dump yard.	59.04	To be quoted by the bidder	Sqm

Terms & Conditions:-

1. The work will be done complete to the entire satisfaction of Engineer-in-Charge of the work.
2. The quantities may be increased or decreased as per site requirement.
3. The GST/taxes shall be charges as per the State Govt. policy as amended from time to time.